

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 23 N. R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corners for T43N R8W ^{13/18}/_{24/19} T43N R7W

CORNER MONUMENT 1 1/2" 30" Iron Pipe buried in left edge of Road,

DATE MONUMENT PLACED AND WITNESSED 9/19/66, Frank J. Bray

WITNESSES TO CORNER..... 12" Beech (S24)(NBT) S 54° W, 93 Links



7" Maple (S18)(NBT) N 78° E, 66 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and single proportioned measurement between section corner 1 mile to North and 2 miles to south.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/26/67
REGISTERED LAND SURVEYOR