

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N. R. 7


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 26/25

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/9/66 - F. J. Bray

WITNESSES TO CORNER..... 3" cedar (X) S 60° W. 05½ links



2" cedar (X) N 02° E. 13 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corners ½ mile to north and to south. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/19/67
REGISTERED LAND SURVEYOR
Frank J. Bray