

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43N N.R. 7W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 16/15

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/15/66 - F. J. Bray

WITNESSES TO CORNER..... 8" S. maple in clump (1/2S) (NBT) N 37° W, 94 1/2 links



6" S. maple in clump (1/2S) (NBT) S 14° E, 64 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corners 1/2 mile to north and to south. Swamp edge to south of corner checks good for distance.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/19/67
REGISTERED LAND SURVEYOR
Frank J. Bray