

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 43 N.R. 7 W

Mackinac COUNTY


DESCRIPTION OF CORNER Section corner for sections

15	14
22	23

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/15/66 - F. J. Bray

WITNESSES TO CORNER..... 10" cedar (S 22) (NBT) S 81° W, 34 1/2 links



9" cedar (S 14) (NBT) N 80° E, 22 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by double proportioned measurement between section corners 1 mile to north, south, east, and west.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/19/67
REGISTERED LAND SURVEYOR
Frank J. Bray