

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N. R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner for Sections ^{10/11} 15/14

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/7/66, Frank J. Bray and R. Lane

WITNESSES TO CORNER..... 9" Cedar (S11)(NBT) N 43° E, 18 Links



6" Cedar (S15)(NBT) S 29° W, 18 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by double proportioned measurement between Section Corners 1 mile to North, East, and West and 2 miles to South.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/19/67
REGISTERED LAND SURVEYOR