

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 5/4

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/19/67, Frank J. Bray

WITNESSES TO CORNER..... 10" H. Maple (1/4S)(NBT) N 18° E, 05 Links



7" H. Maple (1/4S)(NBT) S 18° W, 23 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corner to North and where corner in lake would be set by double proportioned measurement to corners 1 mile to North, South, East and West.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/2/67
REGISTERED LAND SURVEYOR