

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections $\frac{5}{8}$

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/24/67, Frank J. Bray

WITNESSES TO CORNER..... 9" Hard Maple (1/4S)(NBT) N 69° W, 27 Links



8" Hard Maple (1/4S)(NBT) S66°E, 30 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corner to West and to where section corner would be set in lake by double proportioned measurement to East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/2/67
REGISTERED LAND SURVEYOR