

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{7}{8}$ 18/17

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/17/67, Frank J. Bray

WITNESSES TO CORNER..... 5" Cedar (S17)(NBT) S 13° E, 49½ Links



7" Cedar (S7)(NBT) N 68° W, 21 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners 1 mile to East, West and South and 2 mile to North.

SURVEYOR'S SEAL

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR

DATE

7/31/67