

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{6}{5}$
 $\frac{7}{8}$

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/18/67, Frank J. Bray

WITNESSES TO CORNER..... 12" H. Maple (S5)(NBT) N 03° E, 38½ Links



CIRCLE CORNER REGISTERED

6" H. Maple (S7)(NBT) S 27° W, 28½ Links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners 1 mile to North, South and West and 2 miles to East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/31/67
REGISTERED LAND SURVEYOR