

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 & 44 N.R. 7W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner for Sections ^{31/32} T44N R7W
6/5 T43N R7W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/28/66 Frank J. Bray

WITNESSES TO CORNER.....8" Tamarack (S32 NBT) N 66° E, 16 Links



8" Cedar (S6 NBT) S 53° W, 37½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed at wood post and 1½" Iron Pipe set by unknown party. Tamarack stump (Tam. 10" S 17° E 32 Links) has axe marks and overgrowth of face no other evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/18/67
REGISTERED LAND SURVEYOR