

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MACKINAC COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> <sup>N.</sup> <del>7</del> , R. <u>7</u> <sup>W.</sup>	<u>G-4</u>
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	, T. <u>43</u> <sup>N.</sup> S., R. <u>7</u> <sup>E.</sup> W.	<u>II-SEC. 9</u>
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> W.	<u>I5-SEC. 9</u>
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

*3 corners*

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, RLS, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4/28/76, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-4; Quarter Corner bet. Secs' 9-10, set by H. Brevoort Jr, D.S.1845. Bearings were: A Beech 10" was marked for Quarter Post.

II-SEC. 9; South-West 1/16 Corner, Section 9.

I5-SEC. 9; West 1/16 Corner, on South side, Sec. 9.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-4; Placed corner in aprox. Road Intersection. Extended a straight line from the West 1/4 Cor, Sec. 9, thru the Center of Section, and intersected the Section Line bet. Secs' 9-10. This is not midway on the mile (bet.9-10) The North 1/2 mile measures = 2,513.05'. The South 1/2 mile measures= 2,745.55'.

II-SEC. 9; Placed Corner at Intersection of lines, quartering the South-West quarter Section.

I5-SEC. 9; Placed Corner midway bet. Sec. Cor.to West and 1/4 Cor. to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4; Buried 7/8"X24" Iron, in Center of Road.  
New Bearings:  
17" Hemlock, East, 52.5° and 16" H. Maple, N50°W, 56.4°.

II-SEC. 9; Placed 1" Pipe With 4" Aluminum Cap, at Corner.  
Bearings:  
9" H.Maple, N20°E, 13.1' and 9" H.Maple, S16°E, 8.3'.

I5-SEC. 9; Placed 1" Pipe with 4" Aluminum Cap, at Corner.  
Bearings:  
9" H.Maple, N85°E, 41.6° and 8" S.Maple Clump, N40°E, 46.5°.


SIGNED BY Billy D. Buckler *Billy D. Buckler* DATE 7/28/76

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887.

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_