

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MACKINAC CO.

*2 corners*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43 N</u> S., R. <u>7 W</u> E.	G- <u>2</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ S., R. _____ E.	G- <u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ S., R. _____ E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 04/29, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

G-2; Quarter Corner bet. Secs; 3-4, set by H. Brevoort, Jr, D.S 1845  
 Bearings were: Beech 10", S74' W, 16LKs and Beech 14" S67'E, 19LKs.  
 G-1; Closing Corner bet. Secs 3-4, set by H. Brevoort, Jr, D.S. 1845.  
 Bearings were: Sugar 14", S37'W, 24LKs and Beech 10", S23'E, 22LKs.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

G-2; Re-established Corner in Center of N-S Road and 33.0' South of Fence line, on South side of Cemetery.  
 G-1; Re-established Corner, 30.4' West of Corner 33/34, T44N. R.7W., on Township line.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**


G-2., Buried 1/2" X 16" Iron in Center of Road.  
 New Bearings: 15" Hard Maple, N76'W, 49.9' and 10" Hard Maple, N87'E, 45.9'  
 G-1., Set Iron Pipe in 1/3" Drill hole in limestone rock.  
 Corner is 30.4' West of Sec. Cor. 33/34, T44N R7W, on the Township line.

SIGNED BY Billy D. Buckler DATE \_\_\_\_\_  
 SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_