

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 N.R. 7W


Mackinac COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 33 and 34.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 4-10-63

WITNESSES TO CORNER..... 10" Jack Pine (¼ S. N.B.T.) N. 51° W., 33 Lks.



8" Red Pine (¼ S. N.B.T.) N. 48° E., 35½ Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner re-established midway and on line bet. Two Sec.  
Cors. No evidence of Original Cor. Corner lies in Pine Planta-  
tion. Found a White Post 2.00 Chs. South and 1.48 Chs.  
West of Cor. marked thus: 383 - T43N - R7W - Sec. 33 -  
NE - SE - 5/9/38

Found evidence of an older survey from this Post.

SURVEYOR'S SEAL

SIGNED Billy O. Buckles DATE 10/14/65  
REGISTERED LAND SURVEYOR