

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 7 W.


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 8-9-16-17.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 3-19-63

WITNESSES TO CORNER..... 7" Cedar (S. 16 N.B.T.) S. 14° E. 05½ Lks.



7" Cedar (S. 9 N. B.T.) N. 41° E. 31 Lks.

5" Cedar (S. 8 N.B.T.) N. 59' W. 27 Lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at remains of a 12" Tamarack corner tree.
Found original marks on two sides of remaining stub. Also, found an
8" Tamarack bearing N.29° E. 24 Lks. which appears to be a bearing
tree, but can find no record of same.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 7-29-63
REGISTERED LAND SURVEYOR
Billy D. Buckler