

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 28-29-32-33

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9-28-62

WITNESSES TO CORNER..... 5" Red Pine (S 28 NBT) N 12° E 12½ links



5" Red Pine (S 33 NBT) S 20° E 25 links

7" Red Pine (S 29 NBT) West 78½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by double proportionate measure from Corners 1½ miles West; 1 mile North; 1 mile South and a blazed line 1 mile East.

Found no evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4-2-64  
REGISTERED LAND SURVEYOR  
Billy D. Buckler