

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner 33-34 on South boundary of Township

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED November 26, 1962

WITNESSES TO CORNER..... 5" Red Pine (S34 NBT) N 22° E 34 Links



7" Jack Pine (S33 NBT) N 45° W 47 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner lies 80 links North of Pipe Line and 89 links West of Road.

Re-established corner on Township line by single proportionate measure between corners 1 mile West and 2 miles East

Corner lies 20 links South of plantation edge.

Note: Closing Corner for Sections 3-4, T 42 N, R 7 W lies 23 links West of this corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 16, 1964
REGISTERED LAND SURVEYOR
Billy D. Buckler