

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43-44 N.R. 6-7W


Chippewa-MacIntac COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 6-1-36-31 also a Township Corner

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9-18-63

WITNESSES TO CORNER..... 10" Cedar (S31 NBT) N27°E 24 lks



6" Cedar (S6 NBT) S6°E 19 1/2 lks.

8" Cedar (S1 NBT) S70°W 41 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced at an old Tamarack Stump bottom. Found numerous blazes at the corner with eligible signatures. Distance West and North to good corners is good, but the Distance East is short. Squared and Scribed 6" Cedar at Corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE 7/30/1964
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR