

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 31/32

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 4/19/67, with Carl Johnson

WITNESSES TO CORNER..... 10" N. Pine (1/4S)(NBT) S 87° E, 25 Links



7" N. Pine (1/4S)(NBT) S 85° W, 32 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corners 1/2 mile to North and to South.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/31/67
REGISTERED LAND SURVEYOR