

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N. R. 7 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner for section ^{30/29} 31/32

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 4/19/67, with Carl Johnson

WITNESSES TO CORNER..... 5" Cedar (S29)(NBT) N 64° E, 51 Links



7" Cedar (S32)(NBT) S 30° E, 54½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners 1 mile to North, East, and South and 1/4 corner 1/2 mile to West. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/31/67
REGISTERED LAND SURVEYOR