

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 N.R. 7W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner for sections  $\frac{18}{17}$   $\frac{19}{20}$

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 11/22/66, Frank J. Bray

WITNESSES TO CORNER..... 8" R. Pine (S20)(NBT) S 01° E, 21 Links



8" R. Pine (S18)(NBT) N 73° W, 25½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners 3 miles to north and to south and 1/4 corners 1/2 mile to west and 1½ miles to East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/28/67  
REGISTERED LAND SURVEYOR