

# LAND CORNER REGORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	4-Sec.15, 8-Sec.15
2. PROPERTY CONTROLL-15 ING IN SECTION _____	T. 43 N. _____ S. _____ R. 7 E. _____ W. _____	11-Sec.15, 12-Sec.15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-10, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- 4-Sec.15 Northwest 1/16 Corner of Section 15.
- 8-Sec.15 West 1/16 Corner of Section 15.
- 11-Sec.15 Southwest 1/16 Corner of Section 15.
- 12-Sec.15 South 1/16 Corner of Section 15.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- 4-Sec.15 Placed Corner at intersection of lines, quartering the quarter section. Corner lies in South edge of Pine Planation.
- 8-Sec.15 Placed corner midway bet. Center Corner to East and 1/4 Corner to West.
- 11-Sec.15 Placed corner at intersection of lines quartering the SW quarter section. Corner lies in SE corner of Piggley Lake.
- 12-Sec.15 Placed corner midway bet. Center Corner and South 1/4 Corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" pipe with 4" aluminium cap at all four corners. Bearings are:

- 4-Sec.15 10" R. Pine, S35°W, 18.4' & 10" R. Pine, N76°W, 46.3' & 8" J. Pine, N82°E, 13.7'.
- 8-Sec.15 20" H. Maple, S13°E, 23.9' & 6" H. Maple, N51°E, 22.3' & 7" H. Maple, S79°W, 2.1' & Concrete Monument, N21°W, 22.5'.
- 11-Sec.15 10" R. Maple, N64°E, 44.9' & 6" W. Pine, N33°E, 58.9'.
- 12-Sec.15 10" H. Maple, S33°E, 7.4' & 10" H. Maple, S77°W, 23.1' & 12" H. Maple, N3°E, 24.3'.

SIGNED BY Billy D. Buckler DATE 9-29-80  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET