

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>3</u> , T. <u>43</u> N. S., R. <u>7</u> E. W.		<u>13, 9</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Eabbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-24, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 13 Southeast 1/16 corner of section 3. Lilly D. Buckler, RLS in 1981. 8" Cedar, S78°W, 20.6' & 16" Cedar, N15°E, 11.2'.
- 9 East 1/16 corner of section 3. Lilly D. Buckler, RLS in 1981. 10" h. Pine, S36°W, 56.4' & 10" h. Pine, S8°E, 59.7'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 13 Corner adjusted to new location of east 1/4 corner of section 4. Corner placed at intersection of lines connecting opposite 1/16 corners.
- 9 Corner adjusted to new location of east 1/4 corner of section 4. Corner placed midway and on line bet. 1/4 corner east and center corner west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNE. Mounment at both corners. Bearings:

- | | |
|--------------------------|------------------------------|
| 13 6" Cedar, West, 11.9' | 9 16" h. Maple, N62°W, 60.6' |
| 16" Cedar, N22°E, 7.3' | 5" Spruce, East, 8.9' |
| 8" Cedar, S68°W, 21.7' | 10" R. Pine, S08°E, 67.9' |
| 4" Cedar, S22°E, 9.5' | 10" h. Pine, S31°W, 63.2' |

SIGNED BY David E. Eabbitt

David E. Eabbitt

DATE 11-21-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)