

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

1 Corner

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> N. <u>X</u> , R. <u>7</u> E. <u>X</u>	<u>G-2</u>
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-25, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-2 East 1/4 corner of section 4. R.L.S. Billy D. Luckler in 1976. 1/2" x 16" iron in center of road. 15" H. Maple, N76°W, 49.9' & 10" H. Maple, N87°E, 45.9'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-2 This cor. was re-established by Billy D. Buckler R.L.S. in 1976, in the center line of the N-S road and 33.0' south of the south fence of the Caffey Cemetery as the Cemetery deed indicates it should be. In the spring of 1983 Eino Sainio R.L.S. came to me and told me that he was convinced that the cemetery fence was actually constructed on the E-W 1/4 line of sec. 4 and not on the south boundary of the cemetery as it should have been. I was very reluctant to believe this at first but a field check of the grave positions (some of which date to 1903 or before) in relation to the fence and a look at the fence itself have convinced me that Mr. Sainio is correct. I have, therefore, as district land surveyor for the Mich. DNR removed the former DNR 1/4 cor. set

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

by Mr. Buckler and have set a new monument, as described, in line with the fence going west on the south side of the Caffey Cemetery and in the center line of the N-S black-top road.

G-2 1" pipe with plastic ELS cap buried in road. Bearings: 10" H. Maple, S55°W, 48.6' & 8" H. Maple, S55°E, 54.1' & 12" H. Maple, S68°W, 54.0' & SE Fence Corner of Caffey Cemetery, N85°W, 33.3'.

SIGNED BY

David E. Babbitt
David E. Babbitt

DATE 11-21-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)