

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ S., R. _____ E. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>9</u> , T. <u>43</u>	N. _____ S., R. <u>7</u> E. _____	<u>5, F-4</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ S., R. _____ E. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-3, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 5 North 1/16 corner of section 9. Not prev. set.
F-4 Center of section 9. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5 Corner set M.P.O.L. between center corner and computed North 1/4 corner of section 9. North 1/4 cor. falls in a very wet marsh and was not set.
F-4 Set at the intersection of the N-S and E-W 1/4 lines of sec. 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe buried at both corners. Bearings:

- | | |
|-----------------------------|--|
| 5 8" H. Maple, N62°E, 65.2' | F-4 Tag in 14" R. Maple, N60°W, 24.46' |
| 8" H. Maple, N82°E, 35.0' | Tag in Power Pole, N86°W, 32.65' |
| 6" H. Maple, S20°E, 59.2' | Tag in 10" H. Maple, S23°W, 86.58' |
| 7" H. Maple, N21°W, 52.1' | Tag in 14" Beech, N68°E, 75.58' |

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 8-18-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)