

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Mackinac Co. 2 Corners.

164

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 43 N. R. 7 E. W.	F-2 ✓
2. PROPERTY CONTROLLING IN SECTION 4	T. 43 N. R. 7 E. W.	12-3F ✓
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-4 & 1-5, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

F-2 Center Corner of Section 4. Not prev. set.

12-3F Witness Corner 1264.34' North of South 1/4 Corner of Section 4. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-2 Corner set at intersection of N-S and E-W 1/4 lines by closed traverse.

12-3F Corner set on North side Strouble Lake on N-S 1/4 line of Section 4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 D.N.R. Monument set at both corners. Bearings:

F-2 6" Tamarack, N24<sup>0</sup>W, 16.2'  
 3" Tamarack, N63<sup>0</sup>E, 3.5'  
 3" Tamarack, S14<sup>0</sup>E, 14.7'  
 4" Tamarack, S30<sup>0</sup>W, 4.0'

12-3F 30" W. Pine, S47<sup>0</sup>E, 23.4'  
 12" Hemlock, S79<sup>0</sup>E, 26.2'  
 10" W. Birch, N16<sup>0</sup>E, 28.3'  
 8" R. Maple, N62<sup>0</sup>W, 20.5'

SIGNED BY

David B. Babbitt  
 David B. Babbitt

DATE 9-17-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: