

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MACKINAC CO.

4 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>X</u> , R. <u>7</u> W.	<u>A-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	T. <u>43</u> N. <u>X</u> , R. <u>7</u> W.	<u>8, 8-4, 3-4</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-3 & 8-23, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-2 West 1/4 Corner of Section 6. Corner was set by Frank J. Bray L.S. on 9-19-66. 12" W. Pine, S21°E, 37 lks. & 7" W. Birch, N35°E, 77 lks.
- 8 West 1/16 Corner of Section 6. Not prev. set.
- 8-4 Witness corner set on West 1/16 Line, NW 1/16 of Sec. 6 is 526.7' North. Not prev. set.
- 3-4 Witness corner set on North 1/16 Line, NW 1/16 of Sec. 6 is 199.0' East. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-2 Re-witness corner as set by Frank Bray, 1966.
- 8 Corner set M.P.O.L. between West 1/4 Corner and computed Center corner of Section 6 by closed traverse.
- 8-4 NW 1/16 Corner of Section 6 computed at center of the NW 1/4 by closed traverse.
- 3-4 NW 1/16 Corner of Section 6 computed at center of the NW 1/4 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner DNR MONT'S.

- | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ul style="list-style-type: none"> A-2 12" W. Pine Dead, S21°E, 24.4' 7" W. Birch, N35°E, 50.8' 8" Cedar, S39°E, 24.2' 6" Cedar, S56°W, 80.2' 5" Cedar, S08°E, 40.3' | <ul style="list-style-type: none"> 8-4 4" W. Birch, N27°W, 14.12' 5" R. Maple, S19°W, 34.70' 12" Beech, S6°E, 37.82' 12" R. Maple Clump, S62°E, 21.82' |
| <ul style="list-style-type: none"> 8 7" H. Maple, S53°E, 19.70' 6" H. Maple, S01°E, 6.53' 12" R. Maple, S81°W, 14.97' 7" H. Maple, N33°W, 9.70' | <ul style="list-style-type: none"> 3-4 6" Maple, S25°E, 19.19' 6" Maple Clump, South, 8.45' 10" Maple, N60°W, 12.87' 7" Maple, N09°W, 20.03' |

SIGNED BY Gerald L. Wiggins
 Gerald L. Wiggins
 SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

DATE 9-10-86

