

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

T43N R7W T42N R7W

For corners in
Hackinac

(County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 7W	L13
	T 43N R 7W	K13
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

41175 43212
41173 43213

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	3	4	5	6	7	8	9	10	11	12	13	14
3	4	5	6	7	8	9	10	11	12	13	14	15
4	5	6	7	8	9	10	11	12	13	14	15	16
5	6	7	8	9	10	11	12	13	14	15	16	17
6	7	8	9	10	11	12	13	14	15	16	17	18
7	8	9	10	11	12	13	14	15	16	17	18	19
8	9	10	11	12	13	14	15	16	17	18	19	20
9	10	11	12	13	14	15	16	17	18	19	20	21
10	11	12	13	14	15	16	17	18	19	20	21	22
11	12	13	14	15	16	17	18	19	20	21	22	23
12	13	14	15	16	17	18	19	20	21	22	23	24
13	14	15	16	17	18	19	20	21	22	23	24	25

I, Stephan J. Szyzkoski, in a field survey on September 17, 1992, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L13) Quarter corner common to Sections 36 T43N-R7W, and 1 T42N-R7W. Corner previously recorded by Frank J. Bray as monumented by a 1" pipe with a 4" aluminum cap in 1966, with the following accessories: 8" Y. Pine (1/4S)(NBT) S47E 64 links, 11" J. Pine (1/4S)(NBT) S69W 26 links.

(K13) Section corner common to Sections 35-36 T43N-R7W, and 1-2 T42N-R7W. Corner previously recorded by Billy D. Buckler as monumented in 1962 by a 1/2"x36" iron bar with the following NBTs: 14" Soft Maple (S35 NBT) N28W 53 links, 4" W. Pine (NBT) S52W 25 links, 5" R. Pine (S1 NBT) S41E 70.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L13) Found a 1" iron pipe with 4" aluminum cap at record bearing and distance from the NBTs noted above. Removed the monument and placed, at it's position, a 1" pipe with a plastic cap stamped "Mich DNR LS 33986" set below the surface to preclude disturbance by proposed road improvements. Marked 2 additional bearing trees as described below.

(K13) Found and accepted a 1/2" iron bar at record bearing and distance from the R. Pine NBT and the stump of the W. Pine NBT noted above. The Maple NBT was not recovered. Marked 3 new bearing trees as noted below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L13) Set a 1"x32" iron pipe with a plastic RLS cap.
Blazed, scribed, and set measuring nails with tags in the following NBTs:
12" J. Pine S86W 52.0'
14" R. Pine East 58.15'
Set measuring nails in the record NBTs:
10" R. Pine S47E 42.7'
14" J. Pine S69W 17.1'

(K13) 1/2" iron bar buried in the center of an E-W road.
Blazed, scribed, and set measuring nails in the following new bearing trees:
5" Maple S36E 21.25'
10" Balsam N40E 22.05'
10" N. Pine S32W 33.3'
Set a measuring nail and tag in the existing record NBT: 8" R. Pine S41E 46.7'.



Signed by Stephan J. Szyzkoski Date 1-27-93
Surveyor's Michigan License No. 33986