

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

#166

For corners in Mackinac <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T 43N R 7W	F12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 33 T 43N R 7W	MC B-4
	S 33 T 43N R 7W	MC F12-5
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10038  
10036  
10037

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	15	16	17	18	19	20	21	22	23	24			
7													
8	19	20	21	22	23	24							
9													
10	29	30	31	32	33	34	35	36					
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyzkoski, in a field survey on March 02, 1992, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(F12) Corner previously recorded by Billy D. Buckler in 1963 as being established and monumented at the intersection of 1/4 lines.  
 (MC B-4) Southwest corner of the North 8 Chains of the Southeast quarter of the Northwest quarter of Section 33. Corner not established in original survey. Found no record of prior monumentation.  
 (MC F11-F12) Southeast corner of the North 8 chains of the Southeast quarter of the Northwest quarter of Section 33. Not established in original survey. Found no record of prior monumentation.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(F12) Found and accepted 1" pipe with 4" tablet set by Buckler with both of his 1963 BT's agreeing.  
 (MC B-4) Established corner on west N-S 1/16 line 528.02' south (8 chains perpendicular to the north E-W 1/16 line) of the unmonumented NW 1/16 corner of Section 33.  
 (MC F11-F12) Established corner on N-S 1/4 line of section 33 528.02' (being 8 chains as measured perpendicular to north E-W 1/16 line) southerly of north 1/16 corner. Found no monumentation at this position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(F12) Found 1" pipe with 4" cast aluminum tablet. S75E 8.9' set nail and tag in 20" W. Pine (obt); S30E 4.25' nail and tag in 5" spruce; S30W 21.17' set nail and tag in 18" W. Pine (obt); N30W 17.7' nail and tag in 9" maple. Blazed and scribed obt's at BH. Blazed and scribed others at BH and base.	(MC B-4) Set a 1"x32" painted iron pipe with 4" cast aluminum MDNR tablet. N36E 9.9' nail and tag in 11" maple; S80E 32.1' nail and tag in 10" maple; S35W 7.8' nail and tag in 9" maple; N55W 13.7' nail and tag in 7" maple. Blazed and scribed all trees at BH ("PC") and base ("BT").	(MC F11-F12) Set 1"x32" painted iron pipe with 4" cast aluminum MDNR tablet. N16E 12.2' nail and tag in 13" W. Pine; S60E 22.7' nail and tag in 12" W. Pine; S48W 5.7' nail and tag in 6" W. Pine; N44W 34.25' nail and tag in 11" W. Pine. All trees blazed and scribed at BH ("PC") and base ("BT").
--	---	--

Signed by Stephan J. Szyzkoski Date 3-16-92  
 Surveyor's Michigan License No. 33986

