

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Mackinac

(County)

Located In: Corner Code #

1. Public Land Survey	T 43N R 7W	J7
	T 43N R 7W	J9
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property In Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 15 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7									●			
8	19	20	21	22	23	24						
9									●			
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 (J7) Quarter corner common to Sections 14-23. Established in 1966 by Frank J. Bray, RLS, midway between Section corners. Set 1" iron pipe with 4" aluminum cap. 5" Cedar N80W 1 link, 10" Hemlock N76E 19 links.  
 (J9) Quarter corner between Sections 23-26. Reestablished in 1967 by Frank J. Bray, RLS, midway between Section corners. Set 1" ID Iron pipe with 4" alum. cap. 5" Cedar N20W 10.5 links, 6" Cedar S35W 08 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (J7) Recovered the 1966 monument in good condition and at record bearing and distance from the 1966 witness trees, both in good condition with overgrown blazes. Made two new witnesses as described below.  
 (J9) Recovered the 1967 monument in good condition and at record bearing and distance from the 1967 witnesses, both in good condition with scribing visible. I used this monument to control a subdivision of Section 23 this date.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J7) Found 1" ID Iron pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 14" Hemlock N81E 13.25' "1/4S" * 8" twin Cedar N70W 1.15' "1/4S" * 7" Cedar S70E 20.1' "1/4S NBT" 9" Maple N27E 13.3' do Bearings are magnetic. Distances are to nail with tag. * denotes 1966 NBT.	(J9) Found 1" ID iron pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 7" Cedar S12W 15.85' "1/4S NBT" 8" Tamarack S74E 4.75' do Set measuring nails in the 1967 NBTs: 8" Cedar S55W 5.6' old scribe visible 6" Cedar N11W 7.35' do Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 4/06/04