

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACKINAC

(County)

Located In:

Corner Code -#

1. Public Land Survey	T	43N	R	8W	E-9
	T	43N	R	8W	E-10
	T		R		
	T		R		
2. Property Controlling in Section	S	28	T	43N R 8W	12
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith Sackett, in a field survey on 8-7 & 8-27, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-9 Section Corner common to 20,21,29,28. Corner placed by Billy D. Buckler, L.S. on 4-30-68. and new witness trees were marked again by Buckler on 4-3-78.
- E-10 1/4 Corner between 28 and 29. Corner placed by Billy D. Buckler, L.S. on 5-8-68. Bearings 11" Cedar, N70°E, 44.0' and 12" Spruce, S62°W, 64.0'.
- 12 South 1/16 Corner of Section 28. Corner placed by Billy D. Buckler, L.S. on 5-8-80. Bearings: 7" W. Pine, S32°E, 12.6' and 16" W. Pine, N40°E, 75.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-9 Witness trees have been cut except 12" W. Birch, S72°E, 51.7'. Placed new Sq. Post and marked new witness trees and new top blaze on S72°E W. Birch.
- E-10 Replaced Iron Pipe with a 1" X 1" X 18" Iron Bar in Center Line of Blacktop. Spruce has been cut. Marked new top blaze on Cedar.
- 12 Placed new Sq. Post along side of monument. Remarkd top blaze on Buckler's two pine witness tress and added two new witness trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------------|---------------------------|---------------------------|
| E-9 1" pipe. | E-10 1"X1"X18" Iron | 12 DNR Monument |
| 14" W. Birch, S72°E, 51.7' | 4" W. Birch, S70°E, 42.7' | 12" W. Pine, S32°E, 12.6' |
| 10" W. Birch, S25°E, 15.25' | 20" Cedar, N70°E, 44.0' | 20" W. Pine, N40°E, 75.2' |
| 10" W. Birch, S81°E, 5.9' | 4" Cedar, N84°E, 47.5' | 10" W. Pine, S03°W, 20.0' |
| 6" Spruce, N80°W, 81.0' | 16" Spruce, N19°W, 125.5' | 5" W. Pine, S80°E, 20.4' |

Signed by

Keith Sackett

Date 10-7-91

Surveyor's Michigan License No. 19006

