

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

MACKINAC

(County)

Located In:

Corner Code #:

1. Public Land Survey	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling In Section	S	<u>28</u>	T	<u>43N</u>	R	<u>8W</u>	<u>11</u>
	S	<u>28</u>	T	<u>43N</u>	R	<u>8W</u>	<u>8</u>
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Keith Sackett, in a field survey on 8-27, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 11 South-West 1/16 Corner of Section 28. Not previously set.  
 8 West 1/16 Corner of Section 28. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 11 Corner placed at intersection of lines quartering the S.W. 1/4 Section.  
 8 Placed corner midway on line between the West 1/4 Corner and Center of Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 DNR Monument placed at both corners.

11 16" Cedar, S76°E, 17.7'  
 7" Cedar, N36°E, 33.1'  
 12" Cedar, N08°W, 15.25'  
 5" Cedar, S18°W, 15.05'

8 10" Twin Maples, N36°W, 8.2'  
 16" W. Pine, N75°W, 25.4'  
 4" Balsam, N63°E, 21.7'  
 10" Twin Maples, S42°W, 10.45'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

Signed by

*Keith Sackett*

Date 10-7-91

Surveyor's Michigan License No. 19006