

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N. R. 8W

Mackinac COUNTY


DESCRIPTION OF CORNER Sec. Corner common to Secs. 9-10-15-16

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6-19-68

WITNESSES TO CORNER..... 9" Cedar (S16 NBT) S41°W 29.7'

7" Cedar (S15 NBT) S25°E 16.1'



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measure to corners north and south.
Position checks with stream to east as well as a good corner one mile to the east.
Corner lies 3.00 chains south of the Strickler Truck Trail.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
Billy D. Buckler, R.L.S. DATE 10-8-68
REGISTERED LAND SURVEYOR