

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43N R. 8-9W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 18-19-13-24.

CORNER MONUMENT 1" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-9-62

WITNESSES TO CORNER..... 13" Soft Maple (S19 NBT) S72°E, 21 links



8" Cedar (S18 NBT) N66°E 20 1/2 links

10" Cedar (S13 NBT) N40°W 51 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by single proportionate measure from corners 1 mile north and 1/2 mile south.

No evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 23, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler