

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR. 8 - 9 West

Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 25 - 30

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 3-19-58

17" white pine S 43°, W 129 links. "4SMBT"

10" hemlock S 34°, E 4½ links. "4SMBT"

Concrete R.O.W. Marker - east 39 links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. Replaced from two original bearing trees. Pine S 28°, W 9 links. Stump cut, found scribe marks inside scar for bearing tree. Tamarack S 64°, W 21 links. Tree down, scribe marks in poor condition. Found by J. Maloach, District Forester. Placed location poster 3/4 chains north on U. 2.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 6-18-59
REGISTERED LAND SURVEYOR