

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 42-43 N.R. 8 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 1-2-35-36

CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 11/6/63 with Ed. Eckart, Ass't. Forester

WITNESSES TO CORNER..... 10" Cedar Stump (S2 NBT), N 24° E, 68 1/2 lks.



12" Cedar Stump (S36 NBT), S 76° W, 57 lks.

Corner lies in old Beaver Dam and 10 lks. North of Sand Ridge

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Single Proportionate Measure from Corners 1/2 mile East and 1 mile West. Found no evidence of Original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 10/19/1964  
REGISTERED LAND SURVEYOR