

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Mackinac Co. 5 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	2-Sec. 29
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	T. <u>43</u> N. S., R. <u>8</u> E. W.	5-Sec. 29
		6-Sec. 29
		9-Sec. 29
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-27-78, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 2-Sec. 29 East 1/16 Corner on North side of Sec. 29.
- 5-Sec. 29 North 1/16 Corner, Section 29.
- 6-Sec. 29 Northeast 1/16 Corner, Section 29.
- 9-Sec. 29 East 1/16 Corner, Section 29.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2-Sec. 29 Placed corner midway bet. $\frac{1}{4}$ Cor to West and Sec. Cor. to East.
- 5-Sec. 29 Placed corner midway and on line bet. $\frac{1}{4}$ cor. to North and Center Corner to South.
- 6-Sec. 29 Placed corner at Center of the Northeast Quarter Section.
- 9-Sec. 29 Placed corner midway and on line with Center Cor. to West and $\frac{1}{4}$ Cor. to North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at all corners.

- 2-Sec. 29 Bearings: 10" S. Maple, S45°E, 42.5' and 6" Spruce, S88°W, 11.1' and 6" Spruce, S8°W, 13.9'
- 5-Sec. 29 Bearings: 6" Cedar, S80°W, 41.3' and 6" Cedar, S20°E, 20.9' and 8" Cedar, N30°E, 12.6'
- 6-Sec. 29 Bearings: 12" W. Birch, N7°W, 76.1' and 8" Spruce, S88°W, 30.8' and Corner lies in SW Corner of clear cut area.
- 9-Sec. 29 Bearings: 18" W. Pine, East, 31.8' and 6" W. Pine, N21°E, 16.1' and 10" W. Pine, S75°W, 14.8'.

SIGNED BY Billy D. Buckler DATE 9-8-78
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____