

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

4 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> ^{N.} S. , R. <u>8</u> ^{W.} E.	<u>F-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	T. <u>43</u> ^{N.} S. , R. <u>8</u> ^{W.} E.	<u>8-Sec.4</u> <u>9-Sec.4</u> <u>11-Sec.4</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7/13, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 8-Sec.4 West 1/16 Corner, Section 4.**
- 9-Sec.4 East 1/16 Corner, Section 4.**
- 11-Sec.4 Southwest 1/16 Corner, Section 4.**
- F-2 Center Corner, Section 4.**


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 8-Sec.4 Placed corner midway between $\frac{1}{2}$ Corner to West and Center Corner to East.**
- 9-Sec.4 Placed corner midway between $\frac{1}{2}$ Corner to East and Center Corner to West.**
- 11-Sec.4 Placed corner at center of Southwest quarter section.**
- F-2 Placed Corner at intersection of lines Connecting opposite $\frac{1}{2}$ Corners.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at all corners.**
- 8-Sec.4 Bearings: 8" H. Maple, S15°E, 19.2' and 14" H. Maple, N18°E, 42.4'**
- 9-Sec.4 Bearings: 8" Cedar, N4°E, 41.0' and 6" Twin Cedar, N26°E, 24.9'.**
- 11-Sec.4 No Witnesses Available. Corner lies in open creek bottom on west edge of small creek.**
- F-2 Bearings: 14" Cedar, S57°W, 42.5' and 12" Maple, N7°E, 16.7' and 8" Maple, S39°E, 24.2'.**

SIGNED BY Billy D. Buckler DATE 9-8-78
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____