

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 N.R. 8W


Mackinac COUNTY

DESCRIPTION OF CORNER  $\frac{1}{4}$  Corner between Sections 16-17

CORNER MONUMENT 1 $\frac{1}{4}$ " x 30" pipe, buried in center of road.

DATE MONUMENT PLACED AND WITNESSED 5/22/68

WITNESSES TO CORNER..... 14" W. Birch ( $\frac{1}{2}$ S NBT) S85°W 70.6'



12" W. Spruce " S54°E 72.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by single proportionate measure to North and South, and on the alignment of a North and South road.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler, R.L.S. DATE 9/25/68  
REGISTERED LAND SURVEYOR