

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 8W


Mackinac COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ Corner between Sections 2-3.

CORNER MONUMENT 1" Pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 5/13/68

WITNESSES TO CORNER..... 14" Red Pine ($\frac{1}{2}$ S NBT) N57°E 93.5'



9" Soft Maple " S35°W 5.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by proportionate measure between
and original corner, $\frac{1}{2}$ mile South and a Section Corner $\frac{1}{2}$
mile North.

Corner placed on West edge of tree planting furrow.

Corner lies 50' North of woods road.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler, R.L.S. DATE 9/25/68
REGISTERED LAND SURVEYOR