

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N. R. 8W


Macackinac COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 23-24

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 5/21/68

WITNESSES TO CORNER..... 30" W. Pine (1/2 S NBT) N33°W 51.2'



15" W. Pine " S2°E 32.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Squared and scribed 7" Spruce at corner.
This corner re-established midway and on line
between two section corners.

No evidence of original corner.
Found some very old blazes on large W. Pine
which I marked as a new witness to N.W.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
Billy D. Buckler, R.L.S. DATE 9/25/68
REGISTERED LAND SURVEYOR