

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N. R. 8W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 14-15-22-23

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 5/14/68

WITNESSES TO CORNER..... 9" B. Spruce (S22 NBT) S63°W 32.1'



8" B. Spruce (S23 NBT) S29°E 34.1'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by proportionate measure between section corners 1 mile to North and South and on line between same corners.

Location agrees with Corners to East and West.

Corner lies $\frac{1}{2}$ chain North of a narrow sand ridge.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler, R.L.S. DATE 9/25/68
REGISTERED LAND SURVEYOR