

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


Mackinac COUNTY
T 43-44N R 8W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 2-3-34-35

CORNER MONUMENT 5/8" iron pin, driven in center of E-W road

DATE MONUMENT PLACED AND WITNESSED 4-10-69

WITNESSES TO CORNER..... 15" W. Birch (NBT) S18°E 45.4'



10" H. Maple (NBT) N23°W 65.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established on E-W road and by single proportionate measure between Sec. Cor. one mile east and quarter corner 1/2 mile west. Distance north to railroad checks close.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4-24-69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing