

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. SW


Mackinac COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 21-22-27-28

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4-29-68

WITNESSES TO CORNER..... 13" cedar (S21 NBT) N15°W 27.0'



9" cedar (S22 NBT) N58° E 3.5'

Squared and scribed 10" cedar at corner.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original witness; a cedar stump bearing S44°W 19 links. Found a log butt with numerous blazes, faces and overgrowth with evidence of scribe marks. Corner lies in a cedar swamp, 1/2 chain south of a sand ridge.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
Billy D. Buckler, R.L.S. DATE 9-20-68
REGISTERED LAND SURVEYOR