

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 N.R. 8W


Mackinac COUNTY

DESCRIPTION OF CORNER ¼ cor. bet. Secs. 26-27

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 4-26-68

WITNESSES TO CORNER..... 7" W. Pine (½ S NBT) S28°W 40.3'



7" W. Pine (½ S NBT) N20°W 111.5'

8" W. Birch (½ S NBT) N81°E 26.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established midway and on line between two Sec. Cors.  
Numerous Hemlock stumps in vicinity but found no evidence of witnesses  
or corner.

Corner is buried on south edge of Orchard Hill Road.  
Set post 6.0' south of corner.

SURVEYOR'S SEAL

SIGNED *Billy B. Buckler*  
Billy B. Buckler, R.L.S. DATE 9-20-68  
REGISTERED LAND SURVEYOR