

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 N. R. 8W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1-2-11-12

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 4/30/68

WITNESSES TO CORNER..... 12" B. Cherry (Sl NBT) N77°E 57.8'



12" Balsam (NBT) N25°E 51.2'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner re-established by record distance to swamp edges to North, South and West. Location checks with Section Corners one mile in all four directions.

Corner lies 100' North of a road.

**SURVEYOR'S SEAL**

SIGNED Billy D. Buckler  
Billy D. Buckler, R.L.S. DATE 9/25/68  
REGISTERED LAND SURVEYOR