

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Mackinac Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>8</u> E. R. <u>8</u> W.	G-10, F-11, F-11A
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-5, 5-20, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**G-10** Quarter Cor. bet. Sec's. 27-28, set by H. Brevoort Jr. D.S. in 1845. Bearings were: Tamarack 3", N33°W, 26 lks. & Tamarack 4", S47°E, 06 lks.

**F-11** Quarter Cor. bet. Sec's. 28-33, set by H. Brevoort Jr. D.S. in 1845. Bearings were: Tamarack 16", S28°E, 33 lks. & Cedar 10", N78°E, 19 lks.

**F-11A** Meander Corner bet. Sec's. 28-33, on Lake Michigan, 15.00 chains, record distance, West of quarter corner. Bearings were: Pine 6, N86°E, 2.55 chs. & Pine 4, N5°W, 1.68 chs.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**G-10** Placed corner on old line of N-S blazes, 12.55' North of a blazed stub. This places the corner 7.85' East of a strait line bet. two corners and midway. Found several lines of blazes, one of which bears West from this corner. Swamp edges check well.

**F-11** Replaced corner from one probable B.T.; a Tam. 16", S28°E, 33 lks. Found no identifying marks.

**F-11A** Restored corner by extending line thru the quarter corner, from Sec. Cor. 27-28-33-34. Corner lies 30' North of centerline, U.S.#2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminum cap at all three corners.

**G-10** New Bearings: 18" W. Pine, S82°E, 60.5' & 18" W. Pine, S11°W, 77.6'. Corner lies in wet spruce, tamarack swamp aprox. 100' from the east edge and 200' South of the Natural gas pipe line clearing.

**F-11** New Bearings: 10" Cedar, N36°E, 26.4' & 9" Cedar, S54°E, 15.2' & 12" Cedar, S58°W, 23.9'.


**F-11A** New Bearings: 6" S. Maple, N15°W, 9.6' & 8" S. Maple, N82°E, 9.8' & 8" W. Pine, S54°E, 31.6' HWY DEPT R.O.W. MARKER, N56°W, 65.7'.

SIGNED BY \_\_\_\_\_

*Billy D. Buckler*  
Billy D. Buckler

DATE 9-29-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

CHIEF OF SURVEY PARTY

DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

DATE \_\_\_\_\_

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET