

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MACKINAC CO.

4 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>43</u> N. S. R. <u>8</u> E. W.	<u>A-2, L-3</u>
2. PROPERTY CONTROLLING IN SECTION	<u>1</u> T. <u>43</u> N. S. R. <u>8</u> E. W.	<u>4, 5</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-6, 9-17, 7-22-85 6-259 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

4 N.W. 1/16 Corner of Section 1. Not prev. set.

5 North 1/16 Corner of Section 1. Not prev. set.

L-3 South 1/4 Corner of Sec. 1. Set by Billy D. Buckler R.L.S. on 6-4-68. 6" H. Maple, S16°W 13.7' & 6" H. Maple, N19°W, 19.7'.

A-2 West 1/4 Corner of Sec. 6. Set by Billy D. Buckler R.L.S. on 6-20-68. 7" Cedar, N7°W, 28.7' & 8" Cedar, N33°E, 40.0'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

4 Corner set at center of NW 1/4 by closed traverse.

5 Corner set M.P.O.L. between N 1/4 Cor. of Sec. 1 and computed center cor. of sec. 1 by closed traverse.

L-3 Cor. set M.P.O.L. between SW Sec. Cor. and SE Sec. Cor. of Sec. 1. A 1 1/2" pipe set by Billy D. Buckler 10-8-68 lies 39.91' North and 1.69' West.

A-2 Replaced cor. as set by Billy D. Buckler L.S. 6-20-68 from two Cedar witness trees.


4	C. Description of monument for corner and accessories established to perpetuate locating the position of the corner	DNR except A-
	16" R. Pine, S59°W, 63.15'	L-3 10" Cedar, N42°W, 36.4' 1" pipe w/pla
	10" Maple, N89°W, 17.6'	12" Maple, N07°W, 58.95' RLS Cap.
	8" Maple, N30°W, 27.5'	4" Cedar, N46°E, 33.4'
	6" J. Pine, N28°E, 24.6'	1 1/2" Iron Pipe, North, 39.95'
		buried in center line road.
5	6" Maple, N43°E, 8.4'	A-2 7" Cedar, N07°W, 28.7'
	6" Maple, S80°E, 32.1'	8" Cedar, N33°E, 40.0'
	4" Maple, South, 28.9'	5" Hemlock, S46°W, 35.6'
	6" Maple, S60°W, 21.7'	12" Maple, S86°E, 47.9'

SIGNED BY

Gerald L. Wiggins
Gerald L. Wiggins

DATE 9-22-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521



FOR STATE AND UNITED STATES AGENCIES: