

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MACKINAC CO.

3 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>43</u> N. R. <u>8</u> W.	<u>E-1, C-1, C-3</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-19 & 7-2, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-1 N.W. Sec. Cor. of Section 4. OBT'S: Ironwood 7, N74°E, 17 lks. & Sugar 15, N48°W, 30 lks.  
 C-1 N.E. Sec. Cor. of Section 6. OBT'S: Beech 6, N9°W, 21 lks. & Beech 6, S57°W, 32 lks.  
 C-3 S.E. Sec. Cor. of Section 6. OBT'S: Hemlock 12, N55°E, 14 lks. & Birch 12, N66°W, 21 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-1 Replaced corner as set by Larry Feindt L.S. in 1974.  
 C-1 Corner set by single proportionate measure between NW Cor. of Sec. 6 and NE cor. of Sec. 5. Old Fence Line running South.  
 C-3 Replaced corner as set by Billy D. Buckler L.S. 6-24-68. 8" W. Birch, S35°W, 18.5' is still alive and 9" Balsam, N12°W, 22.2' which is now dead.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner DNR except E-

- E-1 1" Pipe W/plastic Cap. C-3 6" Cedar, S23°E, 45.1'  
 DNR Mont., S45°E, 33.0' 5" Cedar, S67°E, 50.0'  
 DNR Mont., N45°E, 33.0' 10" Maple, N13°E, 27.7'  
 1" Pipe w/plastic cap Cor. for T44N R8W 8" W. Birch, S35°W, 18.5'  
 Sec's. 32-33, 15.84' West. 9" Dead Balsam, N12°W, 22.2'  
 Stop Sign, N15°W, 51.8'  
 C-1 R.R. Track, South, 8.65'  
 DNR Mont for Sec. 31-32, T44N R8W,  
 West, 14.56'  
 12" Cedar, S1°W, 66.6'  
 8" B. Ash, S20°W, 69.1'

SIGNED BY

Gerald L. Wiggins  
 Gerald L. Wiggins

DATE 9-22-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

