

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MACKINAC CO.

3 CORNERS.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. <u>XX</u> R. <u>8</u> <u>XX</u> W.	<u>D-7, A-7, A-6</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-6 & 4-12, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- D-7** South 1/4 Corner of Section 17. Corner placed by Billy D. Buckler R.L.S. on 8-1-78. DNR Pipe with 14" W. Birch, S20°E, 26.4' & 12" W. Birch, S63°W, 33.1' & Twin 10" W. Birch, N74°E, 23.2'
- A-7** S.W. Sec. Corner of Section 18. Corner placed by Billy D. Buckler R.L.S. on 8-9-62 DNR Pipe with 13" Soft Maple, S72°E, 21 links & 8" Cedar, N66°E, 20 1/2 links & 10" Cedar, N40°W, 51 links.
- A-6** West 1/4 Corner of Section 18. Corner placed by Billy D. Buckler R.L.S. on 8-9-62. DNR Monument with 10" Aspen N84°W, 19 links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-7** Marked new witness trees, Buckler's bearing trees have been cut.
- A-7** Marked new witness trees at corner as set by Buckler.
- A-6** Marked new witness trees at corner as set by Buckler.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**DNR MONUMENT AT ALL THREE CORNERS.**

- D-7** 16" Maple, S38°E, 58.7' & 6" Balsam, N13°E, 32.7' & 4" Balsam, N43°E, 38.4' & 18" Pine Stump, N8°E, 10.6'.
- A-7** Buckler's 13" Soft Maple is a dead stump standing, the 8" Cedar is dead and down, the 10" Cedar, N40°W, 33.66' is ok. New Trees: 12" Cedar, S13°W, 57.2' & 6" Maple, S69°E, 6.7' & 8" Cedar, N58°E, 29.2'.
- A-6** 10" Cedar, S46°E, 61.3' & 6" Cedar, N72°W, 56.7' & 8" Balsam, S70°E, 47.5' & 8" Balsam, N50°E, 25.1'.

SIGNED BY Gerald L. Wiggins DATE 6-30-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET