

84

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

Located In:

Corner Code #

(County)

1. Public Land Survey

T 43N R 8W K3

T 43N R 8W K2

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Aug 29 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2					●	1	
3											●		
4		7	8	9	10	11						12	
5													
6		18	17	16	15	14						13	
7													
8		19	20	21	22	23						24	
9													
10		30	29	28	27	26						25	
11													
12		31	32	33	34	35						36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Corner common to Sections 1-2-11-12. Corner reestablished in 1968 by Billy D. Buckler, RLS: "This corner reestablished by record distance to swap edges to North, South and West. Location checks with Section Corners one mile in all four directions. Set 1" pipe with 4" aluminum cap. 12" B. Cherry N77E 57.8', 12" Balsam N25E 51.2".

(K2) Quarter corner common to Sections 1-2. Corner reestablished by single proportionate measure between Section corners north and south in 1968 by Billy D. Buckler, RLS. 1" pipe with 4" Aluminum cap and the following new bearing trees: 9" Cedar S36W 17.2', 8" Cedar N48W 3.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) Found and accepted Buckler's monument as described, in good condition, and at record bearing and distance from the remaining 1968 witness Black Cherry. The Balsam witness is dead and down. Left the monument in place, re-marked a top blaze on the cherry, marked three new witnesses, and placed measuring nails in all.

(K2) Found Buckler's monument as described, in good condition, and at record bearing and distance from his 1968 witnesses, both in good condition with scribing visible on upper faces. I determined the monument to be 0.66' North and 0.02' West of the proportionate position and accepted same as a careful and faithful determination of the position of the corner. Left the monument in place, marked two new witnesses and placed measuring nails in all.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

16" B. Cherry N77E 51.75' "S1"
10" Balsam S67E 33.65' "S12 NBT"
6" Spruce N08W 37.0' "S2 NBT"
5" Balsam N10E 33.7' "S1 NBT"

Placed location poster on post 03' south of the corner, on north edge of road. Bearings are magnetic.

(K2) Found 1" pipe with 4" MDNR cap.

The 1968 witnesses:
10" Cedar S36W 16.8'
9" Cedar N48W 3.95'

(bearings are record)

Blazed and scribed the following:

10" Cedar S40W 11.05' "1/4S NBT"
10" Cedar S78E 18.55' "1/4S NBT"

Bearings magnetic. A 4" squared and scribed cedar post was found adjacent.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11-28-95

For the Michigan Department of Natural Resources - Forest Management Division